

GridLock coordination report

Prepared: 9/26/2026, 11:15:16 PM

Filters: Distance band: Touching / crossing

Timeline emphasis: All years

Timeline emphasis does not change ranked or exported rows. Coordination opportunities and shared assets are unverified. Estimates are for discussion only; no realized savings are claimed.

Overlap #1

Why these projects appear together

0.0 km · Touching / crossing

- Shared named endpoint
- Approximate locations: possibly touching.
- Timing: same year. Sharing is not verified.

Pair evidence

The Okatie–McIntosh 115 kV tie line names McIntosh as an endpoint. The DESC series reactor work is at new Deerfield Switching Station, location not stated; the SERTP relay work is at the McIntosh 230 kV bus (SCRTP Planned Facilities 2026-2030 \$2M & Above, p. 41; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 107).

Verify work locations before reviewing possible coordination; shared assets unverified. Their job types could also share a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management.

0 years apart

not stated

Nearest mapped distance: 0.0 km

Okatie – McIntosh 115kV Tie: Add Series Reactor

Dominion Energy SC

SCRTP Planned Facilities 2026-2030 \$2M & Above, p. 41

- In service: 12/31/2028
- Plan cost: \$5,376,418

Source text

Construct Deerfield Switching Station and Install a 9% series reactor on the Okatie – McIntosh 115kV Tie Line.

This project is needed to improve system performance and to meet NERC TPL and internal DESC Planning Criteria for reliability.

Status: Planned

Location: approximate

- Shown as a mapped line.
- Construction limits are not verified.

Location sources

Straight line between Hand-placed from HIFLD Electric Power Transmission Lines, archived line feature (committed source file); SC RTP Planned Facilities 2026-2030, pp. 11-12: INFERRED - junction on the Jasper-Yemassee 230 kV line (HIFLD archived line feature); DESC plans to fold that line into Okatie. Verify on Dominion's Jasper-Okatie route map. / OpenStreetMap

MCINTOSH 230 KV, BREAKER CONTROL RELAY UPGRADES

Georgia Power (inferred)

SC RTP 2025 Regional Transmission Plan (Nov 26 2025), p. 107

- In service: 2028
- Plan cost: not stated

Source text

Replace existing twenty 230 kV breaker control relays with twenty high speed breaker control relays at the McIntosh 230 kV breaker and a half bus.

Protection analysis identified the project modifications are required due to the interconnection of the proposed generating facility.

Status: not stated

Location: exact

- Shown as a mapped point.
- Construction limits are not verified.

Location sources

OpenStreetMap (McIntosh Substation)

Screening savings

Possible saving (estimate): \$62,000 to \$264,000

- Only costs both job types need at this distance count; the low end keeps sharing with a public precedent.
- Team estimate, 2026-09-26: team unit costs by job type and distance.
- Not verified: the plans do not show shared work.

How we estimated this

Team unit-cost file, 2026-09-26: shareable cost items by job type and distance, priced from MISO's transmission cost guide (escalated to 2026 at 4% a year) and public land, wage and rental sources. Saving rates are team assumptions, not measured savings or evidence of a shared asset.

Team unit-cost estimate: two equipment jobs that touch could share a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (equipment job: sized to its printed cost of \$5,376,418; equipment job: sized as one added 230 kV breaker position). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.

How this pair ranks

Score 5.8 = touching (4) × same year (1.0) × one location approximate (0.8) × crosses the state line (1.5) × savings up to \$264,000 (1.21)

- Distance counts most: savings add at most 30%, so with the rest equal a closer pair ranks higher.

- Filters hide pairs; they never change a score or rank.

How the score works

Distance band: touching 4, under 1.6 km 3, under 8 km 2, under 40 km 1. Timing: same year 1.0, 1 year apart 0.7, 2 years 0.4, 3 or more 0.1, a year unknown 0.3. Location: 1.0 for each exact project and 0.8 for each approximate one. State line: 1.5 when the projects are in different states. Savings: 1 plus up to 0.3, growing with the top of the savings range (0.15 at \$100,000, the full 0.3 from \$1,000,000).

Coordination status

Team assumptions

Team unit-cost file, 2026-09-26: shareable cost items by job type and distance, priced from MISO's transmission cost guide (escalated to 2026 at 4% a year) and public land, wage and rental sources. Saving rates are team assumptions, not measured savings or evidence of a shared asset.

Ranked overlaps

46 ranked overlaps

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
1	Okatie – McIntosh 115kV Tie: Add Series Reactor Utility: Dominion Energy SC In service: 12/31/2028 Year: 2028 Accuracy: approximate <u>SCRTP Planned Facilities 2026-2030 \$2M & Above, p. 41</u>	MCINTOSH 230 KV, BREAKER CONTROL RELAY UPGRADES Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 107</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Shared named endpoint Source evidence: The Okatie–McIntosh 115 kV tie line names McIntosh as an endpoint. The DESC series reactor work is at new Deerfield Switching Station, location not stated; the SERTP relay work is at the McIntosh 230 kV bus (SCRTP Planned Facilities 2026-2030 \$2M & Above, p. 41; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 107).	\$62,000 to \$264,000 estimate Team unit-cost estimate: two equipment jobs that touch could share a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (equipment job: sized to its printed cost of \$5,376,418; equipment job: sized as one added 230 kV breaker position). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
2	Okatie – McIntosh 115kV Tie: Add Series Reactor Utility: Dominion Energy SC In service: 12/31/2028 Year: 2028 Accuracy: approximate <u>SCRTP Planned Facilities 2026-2030 \$2M & Above, p. 41</u>	SAV: GOSHEN (SAV) – MCINTOSH 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power In service: 2028 Year: 2028 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 111</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Shared named endpoint Source evidence: Both plans name McIntosh as an endpoint of a 115 kV line. The SERTP rebuild covers the 6.7-mile Goshen (Savannah)–Georgia Pacific (Rincon) section; the mapped full Goshen–McIntosh line endpoint does not establish work at McIntosh. The DESC series reactor work is at new Deerfield Switching Station, location not stated (SCRTP Planned Facilities 2026-2030 \$2M & Above, p. 41; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 111).	\$62,000 to \$191,000 estimate Team unit-cost estimate: an equipment job and a line rebuild that touch could share a laydown yard and joint engineering and project management (equipment job: sized to its printed cost of \$5,376,418; line rebuild: 6.7 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
4	GTC: DRESDEN 500 KV, BUS EXPANSION Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68</u>	MEAG: DRESDEN – LAGRANGE PRIMARY 230 KV, UPGRADE AND JUMPER REPLACEMENT Utility: MEAG Power In service: 2026 Year: 2026 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Shared named endpoint Source evidence: Both plans name DRESDEN as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72). The physical work location is unverified.	No estimate: the plans do not size this pair, or these job types share nothing at this distance. Neither plan gives a length or cost to size this pair; no savings estimate.	
5	MEAG: DRESDEN – LAGRANGE PRIMARY 230 KV, UPGRADE AND JUMPER REPLACEMENT Utility: MEAG Power In service: 2026 Year: 2026 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72</u>	LAGRANGE – NORTH OPELIKA TS 230 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same approximate area Source evidence: Mapped geometries meet, but at least one placement is approximate; physical contact and shared assets are unverified.	\$109,000 to \$351,000 estimate Team unit-cost estimate: a new line and a project of unstated scope that touch could share part of their costs (new line: 16.5 stated miles). The other project's size is not stated, so it adds nothing. The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
6	GTC: NEW TENASKA – WANSLEY 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124</u>	WANSLEY 500 KV, OVERSTRESSED BREAKER REPLACEMENTS Utility: Georgia Power (inferred) In service: 2029 Year: 2029 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 133</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same named substation Source evidence: Both plans name WANSLEY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 133). Shared equipment is not established.	\$40,000 to \$126,000 estimate Team unit-cost estimate: a new line and an equipment job that touch could share a laydown yard and joint engineering and project management (new line: 5 stated miles; equipment job: sized as one added 230 kV breaker position). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
7	GTC: NEW TENASKA – WANSLEY 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124</u>	WANSLEY 500 KV, OVERSTRESSED BREAKER REPLACEMENTS Utility: Georgia Power (inferred) In service: 2029 Year: 2029 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 133</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same named substation Source evidence: Both plans name WANSLEY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 133). Shared equipment is not established.	\$40,000 to \$126,000 estimate Team unit-cost estimate: a new line and an equipment job that touch could share a laydown yard and joint engineering and project management (new line: 5 stated miles; equipment job: sized as one added 230 kV breaker position). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
8	ASHLEY PARK-WANSLEY 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Power (inferred) In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 114</u>	GTC: NEW TENASKA – WANSLEY 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same named substation Source evidence: Both plans name WANSLEY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 114; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124). Shared equipment is not established.	\$4,583,000 to \$8,030,000 estimate Team unit-cost estimate: two new lines that touch could share land and permits, clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (new line: 35 stated miles; new line: 5 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
9	GTC: LAGRANGE – NORTH OPELIKA 230 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68	LAGRANGE – NORTH OPELIKA TS 230 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same named substation Source evidence: Both plans name LAGRANGE work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72). Shared equipment is not established.	\$1,890,000 to \$3,312,000 estimate Team unit-cost estimate: two new lines that touch could share land and permits, clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (new line: 16.5 stated miles). The other project's size is not stated, so it adds nothing. The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
10	GTC: LAGRANGE – NORTH OPELIKA 230 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68	MEAG: DRESDEN – LAGRANGE PRIMARY 230 KV, UPGRADE AND JUMPER REPLACEMENT Utility: MEAG Power In service: 2026 Year: 2026 Accuracy: exact SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same approximate area Source evidence: Mapped geometries meet, but at least one placement is approximate; physical contact and shared assets are unverified.	No estimate: the plans do not size this pair, or these job types share nothing at this distance. Neither plan gives a length or cost to size this pair; no savings estimate.	
11	GRID: ARKWRIGHT – LLOYD SHOALS 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia ITS (joint) In service: 2027 Year: 2027 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 82	LLOYD SHOALS 115 KV LIMITING ELEMENTS, REMOVAL Utility: Georgia Power (inferred) In service: 2027 Year: 2027 Accuracy: exact SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 92	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Shared named endpoint Source evidence: Both plans name LLOYD SHOALS as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 82; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 92). The physical work location is unverified.	No estimate: the plans do not size this pair, or these job types share nothing at this distance. Neither plan gives a length or cost to size this pair; no savings estimate.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
12	GORDON – N DUBLIN 115 KV (GORDON – ENGL MCI J) TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 66</u>	GTC: GORDON – SANDERSVILLE #1 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Shared named endpoint Source evidence: Both plans name GORDON as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 66; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68). The physical work location is unverified.	\$82,000 to \$307,000 estimate Team unit-cost estimate: two line rebuilds that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (line rebuild: 6 stated miles; line rebuild: 1.87 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
13	GTC: HICKORY LEVEL – VILLA RICA 230 KV TRANSMISSION LINE, RECONDUCTOR Utility: Georgia Transmission Corp. In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 85</u>	SUMMER LAKE – VILLA RICA 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 94</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same named substation Source evidence: Both plans name VILLA RICA work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 85; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 94). Shared equipment is not established.	\$69,000 to \$198,000 estimate Team unit-cost estimate: a reconductoring job and a line rebuild that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (reconductoring job: 8.6 stated miles; line rebuild: 2.5 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
14	GTC: DOUGLASVILLE – VILLA RICA 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 83</u>	SUMMER LAKE – VILLA RICA 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 94</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 0 years Touch reason: Same named substation Source evidence: Both plans name VILLA RICA work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 83; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 94). Shared equipment is not established.	\$52,000 to \$195,000 estimate Team unit-cost estimate: two line rebuilds that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (line rebuild: 2.5 stated miles; line rebuild: 2.5 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
15	VILLA RICA SUBSTATION, UPGRADES Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 112</u>	GTC: HICKORY LEVEL – VILLA RICA 230 KV TRANSMISSION LINE, RECONDUCTOR Utility: Georgia Transmission Corp. In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 85</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Same named substation Source evidence: Both plans name VILLA RICA work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 85; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 112). Shared equipment is not established.	\$12,000 to \$72,000 estimate Team unit-cost estimate: a reconductoring job and a substation upgrade that touch could share a laydown yard and joint engineering and project management (reconductoring job: 8.6 stated miles; substation upgrade: sized as one added 230 kV breaker position). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
16	VILLA RICA SUBSTATION, UPGRADES Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 112</u>	GTC: DOUGLASVILLE – VILLA RICA 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 83</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Same named substation Source evidence: Both plans name VILLA RICA work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 83; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 112). Shared equipment is not established.	\$22,000 to \$69,000 estimate Team unit-cost estimate: a line rebuild and a substation upgrade that touch could share a laydown yard and joint engineering and project management (line rebuild: 2.5 stated miles; substation upgrade: sized as one added 230 kV breaker position). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
17	GTC: NEW TENASKA – WANSLEY 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124</u>	CAVENDER DRIVE – WANSLEY 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Power (inferred) In service: 2030 Year: 2030 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 138</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Same named substation Source evidence: Both plans name WANSLEY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 138). Shared equipment is not established.	\$4,812,000 to \$8,431,000 estimate Team unit-cost estimate: two new lines that touch could share land and permits, clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (new line: 5 stated miles; new line: 37 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
18	GTC: CLARKSBORO – WINDER PRIMARY 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121	JEFFERSON ROAD – WINDER PRIMARY 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2030 Year: 2030 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 147	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Shared named endpoint Source evidence: Both plans name WINDER PRIMARY as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 147). The physical work location is unverified.	\$260,000 to \$976,000 estimate Team unit-cost estimate: two line rebuilds that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (line rebuild: 14 stated miles; line rebuild: 11 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
19	GTC: DAWSON CROSSING – NELSON (BLACK) TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 122	DU: DAWSON CROSSING – NELSON (WHITE) 115 KV TRANSMISSION LINE, REBUILD Utility: Dalton Utilities In service: 2030 Year: 2030 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 139	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Same named substation Source evidence: Both plans name DAWSON CROSSING work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 122; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 139). Shared equipment is not established.	\$241,000 to \$905,000 estimate Team unit-cost estimate: two line rebuilds that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (line rebuild: 7.5 stated miles; line rebuild: 15.7 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
20	LLOYD SHOALS – PORTERDALE PRIMARY 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 106	GRID: ARKWRIGHT – LLOYD SHOALS 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia ITS (joint) In service: 2027 Year: 2027 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 82	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Shared named endpoint Source evidence: Both plans name LLOYD SHOALS as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 82; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 106). The physical work location is unverified.	\$164,000 to \$617,000 estimate Team unit-cost estimate: two line rebuilds that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (line rebuild: 15.8 stated miles). The other project's size is not stated, so it adds nothing. The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
21	GTC: CLARKSBORO – WINDER PRIMARY 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121	LAWRENCEVILLE – WINDER PRIMARY 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2030 Year: 2030 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 148	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Same named substation Source evidence: Both plans name WINDER PRIMARY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 148). Shared equipment is not established.	\$158,000 to \$593,000 estimate Team unit-cost estimate: two line rebuilds that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (line rebuild: 14 stated miles; line rebuild: 1.2 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
22	ARKWRIGHT, BUS AND JUMPER REPLACEMENT Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: exact SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 61	GRID: ARKWRIGHT – LLOYD SHOALS 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia ITS (joint) In service: 2027 Year: 2027 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 82	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Shared named endpoint Source evidence: Both plans name ARKWRIGHT as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 61; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 82). The physical work location is unverified.	No estimate: the plans do not size this pair, or these job types share nothing at this distance. Neither plan gives a length or cost to size this pair; no savings estimate.	
25	GTC: BARNESVILLE PRIMARY – THOMASTON 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 120	MEAG: BARNESVILLE PRIMARY 230/115 KV BANK B, REPLACEMENT Utility: MEAG Power In service: 2030 Year: 2030 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 149	Distance: 0.0 km Band: Touching / crossing Year gap: 1 years Touch reason: Shared named endpoint Source evidence: Both plans name BARNESVILLE PRIMARY as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 120; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 149). The physical work location is unverified.	\$80,000 to \$262,000 estimate Team unit-cost estimate: a line rebuild and a project of unstated scope that touch could share part of their costs (line rebuild: 13.24 stated miles). The other project's size is not stated, so it adds nothing. The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
26	PLANT YATES 230 KV BREAKER AND HALF SUBSTATION, REBUILD Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 109</u>	GTC: YATES – LINE CREEK (GREEN) 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Nearby mapped locations Source evidence: Mapped geometries meet; the plans do not establish a shared asset.	\$107,000 to \$347,000 estimate Team unit-cost estimate: an equipment job and a line rebuild that touch could share a laydown yard and joint engineering and project management (equipment job: sized as one added 230 kV breaker position; line rebuild: 16.5 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
27	PLANT YATES 230 KV BREAKER AND HALF SUBSTATION, REBUILD Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 109</u>	GTC: YATES – LINE CREEK (RED) 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 147</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Nearby mapped locations Source evidence: Mapped geometries meet; the plans do not establish a shared asset.	\$107,000 to \$347,000 estimate Team unit-cost estimate: an equipment job and a line rebuild that touch could share a laydown yard and joint engineering and project management (equipment job: sized as one added 230 kV breaker position; line rebuild: 16.5 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
29	GORDON 115 KV, OVERSTRESSED BREAKER REPLACEMENT Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 102</u>	GTC: GORDON – SANDERSVILLE #1 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Shared named endpoint Source evidence: Both plans name GORDON as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 102). The physical work location is unverified.	\$18,000 to \$57,000 estimate Team unit-cost estimate: a line rebuild and an equipment job that touch could share a laydown yard and joint engineering and project management (line rebuild: 1.87 stated miles; equipment job: sized as one added 230 kV breaker position). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
30	GTC: CLARKSBORO – WINDER PRIMARY 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121	LAWRENCEVILLE – WINDER PRIMARY 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2027 Year: 2027 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 89	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Same named substation Source evidence: Both plans name WINDER PRIMARY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 89; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121). Shared equipment is not established.	\$306,000 to \$1,147,000 estimate Team unit-cost estimate: two line rebuilds that touch could share clearing, access roads and mats, a laydown yard, crew and equipment moves, bulk material buying and joint engineering and project management (line rebuild: 15.4 stated miles; line rebuild: 14 stated miles). The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
34	UNION CITY – LINE CREEK – YATES 230 KV TRANSMISSION LINES, REBUILD Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 112	GTC: UNION CITY, LINE TRAP REPLACEMENT Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Same named substation Source evidence: Both plans name UNION CITY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 112; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146). Shared equipment is not established.	\$141,000 to \$464,000 estimate Team unit-cost estimate: a line rebuild and a project of unstated scope that touch could share part of their costs (line rebuild: 23.4 stated miles). The other project's size is not stated, so it adds nothing. The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
35	MEAG: DRESDEN – LAGRANGE PRIMARY 230 KV, UPGRADE AND JUMPER REPLACEMENT Utility: MEAG Power In service: 2026 Year: 2026 Accuracy: exact SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72	CORN CRIB – LAGRANGE 115 KV TRANSMISSION LINE, RECONDUCTOR Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 99	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Same approximate area Source evidence: Mapped geometries meet, but at least one placement is approximate; physical contact and shared assets are unverified.	No estimate: the plans do not size this pair, or these job types share nothing at this distance. Neither plan gives a length or cost to size this pair; no savings estimate.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
37	GTC: BARNESVILLE – SOUTH GRIFFIN 230 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 120</u>	BARNESVILLE AREA 115 KV, NETWORK SOLUTION Utility: Georgia Power (inferred) In service: 2031 Year: 2031 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 152</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Same named substation Source evidence: Both plans name BARNESVILLE work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 120; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 152). Shared equipment is not established.	\$126,000 to \$404,000 estimate Team unit-cost estimate: a new line and a project of unstated scope that touch could share part of their costs (new line: 19 stated miles). The other project's size is not stated, so it adds nothing. The low end counts only items with public precedent; direct costs before contingency; shared savings unverified.	
49	GTC: LAGRANGE – NORTH OPELIKA 230 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68</u>	CORN CRIB – LAGRANGE 115 KV TRANSMISSION LINE, RECONDUCTOR Utility: Georgia Power (inferred) In service: 2028 Year: 2028 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 99</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 2 years Touch reason: Same named substation Source evidence: Both plans name LAGRANGE work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 99). Shared equipment is not established.	No estimate: the plans do not size this pair, or these job types share nothing at this distance. Neither plan gives a length or cost to size this pair; no savings estimate.	
193	GTC: DRESDEN 230 KV, BREAKER REPLACEMENTS Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 123</u>	MEAG: DRESDEN – LAGRANGE PRIMARY 230 KV, UPGRADE AND JUMPER REPLACEMENT Utility: MEAG Power In service: 2026 Year: 2026 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 3 years Touch reason: Shared named endpoint Source evidence: Both plans name DRESDEN as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 123). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 3 years apart; no savings estimate.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
194	GTC: DRESDEN 230 KV, JUMPER REPLACEMENT Utility: Georgia Transmission Corp. In service: 2031 Year: 2031 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 154</u>	MEAG: DRESDEN – LAGRANGE PRIMARY 230 KV, UPGRADE AND JUMPER REPLACEMENT Utility: MEAG Power In service: 2026 Year: 2026 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 5 years Touch reason: Shared named endpoint Source evidence: Both plans name DRESDEN as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 154). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 5 years apart; no savings estimate.	
210	GTC: CLARKSBORO – WINDER PRIMARY 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121</u>	WINDER PRIMARY 230 KV, BREAKER INSTALLATION Utility: Georgia Power (inferred) In service: 2033 Year: 2033 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 163</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 4 years Touch reason: Same named substation Source evidence: Both plans name WINDER PRIMARY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 121; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 163). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 4 years apart; no savings estimate.	
211	GTC: DRESDEN – TALBOT 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 122</u>	MEAG: DRESDEN – LAGRANGE PRIMARY 230 KV, UPGRADE AND JUMPER REPLACEMENT Utility: MEAG Power In service: 2026 Year: 2026 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 3 years Touch reason: Shared named endpoint Source evidence: Both plans name DRESDEN as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 72; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 122). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 3 years apart; no savings estimate.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
212	GTC: NEW TENASKA – WANSLEY 500 KV, NEW TRANSMISSION LINE, CONSTRUCT Utility: Georgia Transmission Corp. In service: 2029 Year: 2029 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124</u>	WANSLEY LINE, PROTECTIVE RELAYING REPLACEMENT Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 3 years Touch reason: Same named substation Source evidence: Both plans name WANSLEY work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 124). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 3 years apart; no savings estimate.	
213	GOLDENS CREEK – WARRENTON PRIMARY 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2030 Year: 2030 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 141</u>	MEAG: RAY PLACE RD – WARRENTON PRIMARY 115 KV TRANSMISSION LINE, RECONDUCTOR Utility: MEAG Power In service: 2027 Year: 2027 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 90</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 3 years Touch reason: Shared named endpoint Source evidence: Both plans name WARRENTON PRIMARY as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 90; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 141). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 3 years apart; no savings estimate.	
214	GTC: EAST WATKINSVILLE 230 KV, REACTOR INSTALLATION Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 144</u>	ATHENA – EAST WATKINSVILLE 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 78</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 3 years Touch reason: Shared named endpoint Source evidence: Both plans name EAST WATKINSVILLE as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 78; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 144). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 3 years apart; no savings estimate.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
215	GTC: YATES – LINE CREEK (GREEN) 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146</u>	UNION CITY – YATES 230 KV (WHITE), SWITCH AND TRAP REPLACEMENT Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 4 years Touch reason: Same named substation Source evidence: Both plans name YATES work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 4 years apart; no savings estimate.	
216	GTC: YATES – LINE CREEK (GREEN) 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146</u>	UNION CITY (WHITE) – YATES 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 4 years Touch reason: Same named substation Source evidence: Both plans name YATES work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 4 years apart; no savings estimate.	
217	GTC: YATES – LINE CREEK (RED) 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 147</u>	UNION CITY – YATES 230 KV (WHITE), SWITCH AND TRAP REPLACEMENT Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 4 years Touch reason: Same named substation Source evidence: Both plans name YATES work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 147). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 4 years apart; no savings estimate.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
218	GTC: YATES – LINE CREEK (RED) 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: exact <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 147</u>	UNION CITY (WHITE) – YATES 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 4 years Touch reason: Same named substation Source evidence: Both plans name YATES work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 77; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 147). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 4 years apart; no savings estimate.	
256	GORDON – SANDERSVILLE #1 115 KV TRANSMISSION LINE (DEEPSTEP-SAND #6), REBUILD Utility: Georgia Power (inferred) In service: 2030 Year: 2030 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 142</u>	GTC: GORDON – SANDERSVILLE #1 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 4 years Touch reason: Shared named endpoint Source evidence: Both plans name GORDON as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 68; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 142). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 4 years apart; no savings estimate.	
257	GTC: UNION CITY, LINE TRAP REPLACEMENT Utility: Georgia Transmission Corp. In service: 2030 Year: 2030 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146</u>	EAST POINT – UNION CITY, FIBER INSTALLATION Utility: Georgia Power (inferred) In service: 2027 Year: 2027 Accuracy: approximate <u>SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 80</u>	Distance: 0.0 km Band: Touching / crossing Year gap: 3 years Touch reason: Shared named endpoint Source evidence: Both plans name UNION CITY as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 80; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 146). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 3 years apart; no savings estimate.	

Rank	Project A / source	Project B / source	Distance / timing / evidence	Screening savings	Coordination status
258	MEAG: ATHENA – WARRENTON 230 KV TRANSMISSION LINE, CONVERSION Utility: MEAG Power In service: 2030 Year: 2030 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 149	ATHENA – EAST WATKINSVILLE 115 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2027 Year: 2027 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 78	Distance: 0.0 km Band: Touching / crossing Year gap: 3 years Touch reason: Shared named endpoint Source evidence: Both plans name ATHENA as an endpoint, and mapped line endpoints meet (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 78; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 149). The physical work location is unverified.	No estimate: project timing is too far apart. In-service years are 3 years apart; no savings estimate.	
259	BAY CREEK – CONYERS 230 KV TRANSMISSION LINE, REBUILD Utility: Georgia Power (inferred) In service: 2031 Year: 2031 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 152	GTC: CONYERS – CORNISH MOUNTAIN 115 KV LINE, UPGRADE Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 67	Distance: 0.0 km Band: Touching / crossing Year gap: 5 years Touch reason: Same named substation Source evidence: Both plans name CONYERS work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 67; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 152). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 5 years apart; no savings estimate.	
260	BAY CREEK – CONYERS 230 KV, LIMITING ELEMENT REPLACEMENT Utility: Georgia Power (inferred) In service: 2033 Year: 2033 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 160	GTC: CONYERS – CORNISH MOUNTAIN 115 KV LINE, UPGRADE Utility: Georgia Transmission Corp. In service: 2026 Year: 2026 Accuracy: approximate SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 67	Distance: 0.0 km Band: Touching / crossing Year gap: 7 years Touch reason: Same named substation Source evidence: Both plans name CONYERS work with stated voltages (SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 67; SERTP 2025 Regional Transmission Plan (Nov 26 2025), p. 160). Shared equipment is not established.	No estimate: project timing is too far apart. In-service years are 7 years apart; no savings estimate.	

Sources and attribution

SCRTP Planned Facilities 2026-2030 \$2M & Above; edition date: not stated. Project citations above identify PDF pages.

SERTP 2025 Regional Transmission Plan (Nov 26 2025); edition date: 2025-11-26. Project citations above identify PDF pages.

Independent student project; not affiliated with Dominion Energy, Georgia Power, Southern Company, GTC, MEAG or Sperry Tech. Estimates are for discussion only.